

University of Kerala
Engineering Unit, Kariavattom

TENDER SCHEDULE FOR THE AIR CONDITIONING WORK OF SETTING UP OF RESOURCE CENTRE IN KERALA UNIVERSITY LIBRARY, PALAYAM						
Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	2	Supply conveyance installation testing and commoissioning of 1.5 TR 3 star split Air Conditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 Hz single phase AC supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with codless remote etc. including refrigerent, electrical cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty, 5 year compressor warranty and one year free service (Voltas/Blue Star/Daikan/Carrier) 100% copper.	E			
2	2	Supply of 4 KVA voltage stabilizer for suplit type AC unit with voltage range of 210-240V (V-Guard)	E			
3	2	Supply and providing condensor stand	Set			
4	10	Supply and providing extra copper pipe, drain pipe with thermal insulation if necessary	m			
5	1	Supply and installation of timer suitable for 1.5 ton 3 star split type AC	E			
		TOTAL				

PAC

I/We agreed to execute the work at quoted rates

CONTRACTOR

sd/-
UNIVERSITY ENGINEER