

University of Kerala
Engineering Unit, Kariavattom

Tender schedule for the Air conditioning works for UPS wiring for Implementation of the file flow management System (FFMS) in University Office. (Retender)

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
	2 nos	Supply conveyance installation testing and commissioning of 2TR 5 star rated Inverter split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R410 A CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electric cable, copper pipe and thermal insulation up to 3 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikin/Carrier/Panasonic/ Mitsubishi) 100% copper	E			

2	2	nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard) with 3 months replacement warranty 3 years on site warranty	E			
3	2	SET	Condensor Stand	SET			
4	12	m	Extra copper pipe wire and thermal insulaton	m			
			TOTAL				

PAC Rs.

I/We agreed at quoted rates.

CONTRACTOR

sd/-
UNIVERSITY ENGINEER