

UNIVERSITY OF KERALA

SUBDIVISION I,KARIAVATTOM

**Tender Schedule for Department of Psychology at Kariyavattom Campus- Laying Floor Tiles in the HOD' s Room, Office Room and Room of the Centre for Geriatric Studies-**

SL No	item Description	Qty	Unit	Rate	Rate in words	Amount
1	od317559/2021_2022 Labour engaged for lifting the furniture shelves etc and rearranging them back after flooring	5	Each	878.78	Rupees Eight hundred Seventy Eight Ps Seventy Eight Only	4393.9
2	11.49.2 Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS : 15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tiles 600x600 mm	88	M2	1895.07	Rupees One Thousand Eight hundred Ninty Five Ps Seven Only	166766.16

3	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	16	M2	99.66	Rupees Ninty Nine Ps Sixty Six Only	1594.56
4	od316929/2021_2022 Labour engaged for removing the door shutters and cutting the same in suitable height and refixing the same	5	Each	1162.26	Rupees One Thousand One Hundred Sixty Two Ps Twenty Six Only	5811.3
<b>Total</b>						<b>178565.92</b>
Round off <b>Rs 1,78,566/-</b> ( Rupees One Lakh Seventy Eight Thousand Five Hundred Sixty Six Only ) Excluding GST						

I/We agree to undertake the above mentioned work:-

1)At the estimate rate

2)At.....% below the estimate rate

3)At.....% above the estimate rate

Rate should be quoted both in figures and words

**CONTRACTOR**

**ASSISTANT EXECUTIVE ENGINEER**