

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

Tender schedule for the work of extension of library in the Department of Psychology at Kariavattom campus.

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	3.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.In cement mortar	m3	1214.57	Rs.One thousand Two hundred & Fourteen & ps. Fifty seven only	3,643.71
2	1.00	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	E	227.49	Rs.Two hundred & Twenty seven & ps. Forty Nine only	227.49
3	10.00	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	m2	249.26	Rs.Two hundred & Forty Nine & ps. Twenty Six only	2,492.60
4	10.00	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer	m2	53.25	Rs.Fifty Three & ps. Twenty Five only	532.50
5	0.80	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	m3	8046.00	Rs.Eight thousand Forty Six only	6,436.80

6	99.00	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).Size of Tile 600x600 mm	m2	1685.56	Rs.One thousand Six hundred & Eighty Five & ps. Fifty Six only	166,870.44
7	260.00	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. One coat	m2	71.12	Rs.Seventy One & ps. Twelve only	18,491.20
8	22.00	Painting with synthetic enamel paint, having VOC (Volatile Organic Compound) content less than 150 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. One coat	m2	71.77	Rs.Seventy One & ps. Seventy Seven only	1,578.94
9	12.00	Labour engaged for lifting furniture , books etc before tiling and rearranging them after tiling	E	616.01	Rs.Six Hundred and Sixteen & ps.One only	7,392.12
		Total				207,665.80

PAC Rs.2,07,666/- (Rs.Two lakh Seven Thousand six Hundred and Sixty Six only)

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

CONTRACTOR

sd/-
UNIVERSITY ENGINEER